



**ILOILO II ELECTRIC COOPERATIVE, INC. (ILECO II)**

Brgy. Cau-ayan, Pototan, Iloilo  
Tel Nos. (033)529-8063, (033)529-8981  
Email add: ileco2bac@yahoo.com

**SUPPLEMENTAL BID BULLETIN**

Addendum No. 1

PUBLIC BIDDING

**Design, Supply, Delivery, Construction, Installation, Testing and Commissioning of 15/18.75 MVA, 69/13.2kV Turnkey Substation for Lublub Substation**


This Addendum No. 1 is issued to clarify and/or amend certain provisions in the Bidding Documents issued for this project.

ADDENDUM No.	REFERENCE	AMENDMENTS/CLARIFICATIONS
	<b>Section III. Bid Data Sheet</b>	<b>Section III. Bid Data Sheet</b>
1	ITB Clause 12.1 The deadline for submission of bids is 05 October 2022, 1:00 p.m.	ITB Clause 12.1 The deadline for submission of bids is <b>14 October 2022, 9:30 a.m.</b>
	ITB Clause 13.1 The date and time of bid opening is 05 October 2022, 1:30 p.m.	ITB Clause 13.1 The date and time of bid opening is <b>14 October 2022, 10:00 a.m.</b>
2	<b>Section VI. Schedule of Requirements</b> Delivery Period: 180 Calendar Days from receipt of Purchase Order (P.O.)	<b>Section VI. Schedule of Requirements</b> Delivery Period: 180 Calendar Days from receipt of <b>Notice to Proceed (NTP)</b>
3	<b>Section VI. Schedule of Requirements</b> 3.8. 69/15KV Protection, Control and Metering Panel with Protection Overcurrent Relays of 69kv & 15kv, SCADA Ready & Meters for 1 incoming & 4 feeders.	<b>Section VI. Schedule of Requirements</b> 3.8. 69/15KV Protection, Control and Metering Panel with Protection Overcurrent Relays of 69kv & 15kv, SCADA Ready & Meters for incoming ( <b>meters for 69kV and main feeder</b> ) & 4 feeders.
	<b>Section VII. Technical Specifications</b>	<b>Section VII. Technical Specifications</b>
4	Item No. 2 69kV Outdoor Protection Equipment US, European or Asia Brand	Item No. 2 69kV Outdoor Protection Equipment <b>US, European Brand</b>
	Item No. 10 15kV, 240 sq. mm XLPE Power Cable Single core 240mm <sup>2</sup> copper stranded conductor, CTS-Copper Tape Screen, PVC UV resistant black outer sheath, 133% I.L., black intended for outdoor use	Item No. 10 15kV, 2x240 sq.mm or <b>500 sq.mm</b> XLPE Power Cable Single core 240mm <sup>2</sup> or 500 mm <sup>2</sup> copper stranded conductor, CTS-Copper Tape Screen, PVC UV resistant black outer sheath, 133% I.L., black intended for outdoor use
	<b>REFERENCE</b>	<b>INCLUSIONS</b>
5	Item 2.5 69kV Lightning Arrester Polymeric housed metal oxide surge arrester having a duty cycle rating of 10 kA. The arrester is self-supporting, suitable for outdoor installation and base mounting only.	The Arrester shall be furnished complete with a discharge/surge counter. The discharge/surge counter shall be fully weather proofed and sealed for life and provided with means enabling the removal of surge counter without disconnecting the surge arrester.
	Civil Works Perimeter fence	Substation switch yard area = 500mm <sup>2</sup> ± 10m Perimeter Fence Area = 823m <sup>2</sup>

The herein amendment forms an integral part of the bidding documents. Correspondingly, all other provisions in the bidding documents affected by this amendment are similarly amended or modified.

This SUPPLEMENTAL/BID BULLETIN ADDENDUM No. 1 is issued this 28th day of September 2022 for guidance and information of all concerned.

  
**MA. UNA P. PADILLA**  
BAC Chairman

  
**REXUS O. LESONDATO**  
Member

  
**RODRIG L. CLAUDIO**  
Member

  
**ROMMIR C. CARO**  
Vice Chairman